MASTERSPEC - SECTION 31 63 16

AUGER CAST GROUT PILE ACCESSORIES

PART 1 - GENERAL

1.1 SUMMARY

Section Includes: Auger cast grout piles and accessories indicated, specified, or required to Α. complete installation.

1.2 SUBMITTALS

- Product Data: Manufacturer's technical product literature for each type of product. Α.
- 1.3 QUALITY ASSURANCE
 - Α. Manufacturer Qualifications: Company specializing in manufacturing products specified with minimum of three years documented experience.

PART 2 - PRODUCTS

- 2.1 MANUFACTURER
 - PIERESEARCH[®], 501 East Main Street, Arlington TX, 76010; phone (817) 277-3738; Α. www.pieresearch.com.
 - Β. For manufacturers not listed, submit as substitution according to the Conditions of the Contract and Division 01 Specification Sections.
- TENDON CENTRALIZERS (QUICK-LOCK[®] UNIBAR[®] CENTRALIZERS) 2.2
 - Α. Description:
 - 1. Devices to center steel reinforcement in excavation; spaced not less than 15 feet o.c. for vertical piles and 10 feet o.c. for battered piles; fits piers 10 to 24 inches in diameter; and fits bar sizes #6 through #18.
 - 2. Centralizer is made of plastic and are two identical halves that can be easily snapped together around tendon.
 - 3. Centralizer keeps tendon centered in pile and does not impede flow of grout/concrete.
 - Β. Centralizer Part Numbers:

NOTE TO SPECIFIER: SELECT ONE OF THE FOLLOWING OPTIONS:

- 1011-6/18UBC: 10/11" O.D. Adjustable Quick-Lock[®] Unibar[®] Centralizer #6 #18 1415-6/18UBC: 14/15" O.D. Adjustable Quick-Lock[®] Unibar[®] Centralizer #6 #18 1617-6/18UBC: 16/17" O.D. Adjustable Quick-Lock[®] Unibar[®] Centralizer #6 #18 1.
- 2.
- 3.

PART 3 - EXECUTION

INSTALLATION 3.1

- A. Attach centralizers to tendon according to manufacturer's instructions.
- B. Snap two pieces together around tendon with one piece being inverted to the other piece.
- C. Attachment Locations:
 - 1. At deep end of pile, attach centralizer at approximately 1 foot from end of the tendon.
 - 2. Attach centralizers at maximum 15 foot intervals along total length of the tendon.
 - 3. At access end of pile, attach centralizer so that it will be approximately 1 foot below grout/concrete surface.
- D. To prevent sliding, secure centralizer to the tendon with tie wire.

END OF SECTION